

Bill of Quantities for Merangkong Tamlu Mon Road

Summary of Bills

Bill No.	Description	Amount (INR) (In Figures)
1	General and Site Clearance	
2	Earthworks	
3	Granular Sub Base and Base Course	
4	Bituminous Works	
5	Culverts	
6	Bridges	
7	Repair of Existing Bridges	
8	Drainage and Protective Works	
9	Road Appurtenances	
10	Miscellaneous	
Total Price		

Project Road: Merangkong Tamlu Mon Road						
Item	Description	Unit	Quantity	Rate (INR) (in Figures)	Rate (INR) (in Words)	Amount (INR) (In Figures)
BILL No. 01: GENERAL and SITE CLEARENCE						
1.01	Clearing and Grubbing of Roadway as per Technical Specification Clause 201.	Ha	153			
1.02	Dismantling of Existing Structures or any Existing Civil Works within Right of Way, as per Technical Specification Clause 202.					
i)	Brick Masonry	cum	NIL			
ii)	Stone Masonry	cum	8,495			
iii)	Lime/Plain Cement Concrete in all grades	cum	825			
iv)	Reinforced / Pre-stressed Cement Concrete in all grades	cum	930			
v)	Bituminous Courses	cum	2,840			
vi)	Non Bituminous Courses	cum	NIL			
vii)	Cement Concrete Pavements	cum	NIL			
viii)	Ordinary KM stone/Guard Stone/Sign Post	Number	50			
ix)	Hectometer Stone	Number	NIL			
x)	5 th KM stone	Number	NIL			
xi)	Kerb stone	m	NIL			
xii)	All types of Fencing including posts, foundation concrete, back filling of pit etc.	m	NIL			

Project Road: Pfutsero Phek Road						
Item	Description	Unit	Quantity	Rate (INR) (in Figures)	Rate (INR) (in Words)	Amount (INR) (In Figures)
112						
10.03	Maintenance of Existing Road as per Technical Specification Section 3000 and Additional Technical Specification A-5					
a	Rain Cut Restoration	m	2,880			
b	Hill Side Drain Clearance	cum	6,500			
c	Land Slide debris Clearance	cum	50,085			
Total of Bill No. 10 Carried Forward to Summary						